

"Beaver River Road Repair Project Bid Form"

| | |
|------------------------------|--|
| Project Number | 2020-01 Beaver River Road |
| Brief Description of Project | Shape, grade, deliver material and install/reset culverts along a 0.3 mile project area. |
| Legal Description | Sections 2/3 - Twp 56 N - Rng 9 W |
| Trout Stream | None |
| Gravel Source | Private / Local |
| Gravel Haul Distance | TBD |

| BID ITEMS | | | | | |
|---------------------|--|-----------------|--------------|-----------------------|------------------|
| Item | Comment | Quantity | Unit | Price per Unit | Total Bid |
| Shape/Grade | Grub and Ditch both sides 1.5'deep x 3' wide. Mound all suitable material on road surface. | 1,653.0 | linear foot | \$ | \$ |
| Grubbing/Ditching | Establishment to include tree/brush removal. | 692.0 | linear foot | \$ | \$ |
| Ditch reinforcement | Class II (6-inch) rip-rap | 30 .0 | cubic yard | \$ | \$ |
| Ditch - clean | Clear of all debris and material | 1,173.0 | linear foot | \$ | \$ |
| Install Culvert | 24" x 36' cross-drain. Cap and compact with 20 cu.yrd. 2"-minus. | 1.0 | installation | \$ | \$ |
| Install Culvert | 18" x 28'. Cap with 15 cu.yrd. 2"-minus. | 1.0 | installation | \$ | \$ |
| Reset Culvert | Station 0-0 & Station 0-10 | 2.0 | culvert | \$ | \$ |
| Gravel (yards) | Pit run. Fill washout. | 100.0 | cubic yard | \$ | \$ |
| Gravel (yards) | Haul, spread and grade according to contract specification. 1 1/2"-minus. | 1175 | cubic yard | \$ | \$ |
| Erosion Control | As needed. See supplemental specification. | 1,653.0 | linear foot | \$ | \$ |
| TOTAL | | | | | \$ |

Each item with a quantity must have a unit cost bid and total cost filled in above. The County reserves the right to increase and/or decrease quantity of delivered material. Contractor shall be paid at bid price for all delivered loads verified by ticket.

ALL BIDS DUE MONDAY AUGUST 3, 2020 BY END OF BUSINESS DAY (4:30 PM).

BIDDER NAME _____

BIDDER ADDRESS _____

PHONE NUMBER _____

